

AD-A105 305

REITZ AND JENS INC ST LOUIS MO
NATIONAL DAM SAFETY PROGRAM. WIGGINS OZARK CAMP DAM (MO 30026) --ETC(U)
DEC 78 H REITZ, J J BAILEY


F/G 13/13

DACW43-78-C-0162

NL

UNCLASSIFIED

1 OF 1
AD A
105305



LEVEL

13 (1)

AD A105305


WHITE BASIN

WIGGINS OZARK CAMP DAM

REYNOLDS COUNTY, MISSOURI

MO 30026

**PHASE 1 INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM**



DTIC
ELECTE
S OCT 8 1981 **D**
F

PREPARED BY: U. S. ARMY ENGINEER DISTRICT, ST. LOUIS

FOR STATE OF MISSOURI

DISTRIBUTION STATEMENT A

**Approved for public release;
Distribution Unlimited**

DECEMBER 1978

DTIC FILE COPY

81 10 8 047

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO. <i>AD-A105 305</i>	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program Wiggins Ozark Camp Dam (MO 30026) Reynolds County, Missouri		5. TYPE OF REPORT & PERIOD COVERED <i>Final Report</i>
7. AUTHOR(s) Reitz & Jens, Inc.		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		8. CONTRACT OR GRANT NUMBER(s) <i>DACW43-78-C-0162</i>
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) <i>6</i> National Dam Safety Program, Wiggins Ozark Camp Dam (MO 30026), White Basin, Reynolds County, Missouri. Phase I Inspection Report.		12. REPORT DATE <i>11</i> December 1978
		13. NUMBER OF PAGES Approximately 45
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT Approved for release; distribution unlimited. <i>12/11/78</i>		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety, Lake, Dam Inspection, Private Dams		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.		


DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)



SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

INSTRUCTIONS FOR PREPARATION OF REPORT DOCUMENTATION PAGE

RESPONSIBILITY. The controlling DoD office will be responsible for completion of the Report Documentation Page, DD Form 1473, in all technical reports prepared by or for DoD organizations.

CLASSIFICATION. Since this Report Documentation Page, DD Form 1473, is used in preparing announcements, bibliographies, and data banks, it should be unclassified if possible. If a classification is required, identify the classified items on the page by the appropriate symbol.

COMPLETION GUIDE

General. Make Blocks 1, 4, 5, 6, 7, 11, 13, 15, and 16 agree with the corresponding information on the report cover. Leave Blocks 2 and 3 blank.

Block 1. Report Number. Enter the unique alphanumeric report number shown on the cover.

Block 2. Government Accession No. Leave Blank. This space is for use by the Defense Documentation Center.

Block 3. Recipient's Catalog Number. Leave blank. This space is for the use of the report recipient to assist in future retrieval of the document.

Block 4. Title and Subtitle. Enter the title in all capital letters exactly as it appears on the publication. Titles should be unclassified whenever possible. Write out the English equivalent for Greek letters and mathematical symbols in the title (see "Abstracting Scientific and Technical Reports of Defense-sponsored RDT/E," AD-667 000). If the report has a subtitle, this subtitle should follow the main title, be separated by a comma or semicolon if appropriate, and be initially capitalized. If a publication has a title in a foreign language, translate the title into English and follow the English translation with the title in the original language. Make every effort to simplify the title before publication.

Block 5. Type of Report and Period Covered. Indicate here whether report is interim, final, etc., and, if applicable, inclusive dates of period covered, such as the life of a contract covered in a final contractor report.

Block 6. Performing Organization Report Number. Only numbers other than the official report number shown in Block 1, such as series numbers for in-house reports or a contractor/grantee number assigned by him, will be placed in this space. If no such numbers are used, leave this space blank.

Block 7. Author(s). Include corresponding information from the report cover. Give the name(s) of the author(s) in conventional order (for example, John R. Doe or, if author prefers, J. Robert Doe). In addition, list the affiliation of an author if it differs from that of the performing organization.

Block 8. Contract or Grant Number(s). For a contractor or grantee report, enter the complete contract or grant number(s) under which the work reported was accomplished. Leave blank in in-house reports.

Block 9. Performing Organization Name and Address. For in-house reports enter the name and address, including office symbol, of the performing activity. For contractor or grantee reports enter the name and address of the contractor or grantee who prepared the report and identify the appropriate corporate division, school, laboratory, etc., of the author. List city, state, and ZIP Code.

Block 10. Program Element, Project, Task Area, and Work Unit Numbers. Enter here the number code from the applicable Department of Defense form, such as the DD Form 1498, "Research and Technology Work Unit Summary" or the DD Form 1634, "Research and Development Planning Summary," which identifies the program element, project, task area, and work unit or equivalent under which the work was authorized.

Block 11. Controlling Office Name and Address. Enter the full, official name and address, including office symbol, of the controlling office. (Equates to funding/sponsoring agency. For definition see DoD Directive 5200.20, "Distribution Statements on Technical Documents.")

Block 12. Report Date. Enter here the day, month, and year or month and year as shown on the cover.

Block 13. Number of Pages. Enter the total number of pages.

Block 14. Monitoring Agency Name and Address (if different from Controlling Office). For use when the controlling or funding office does not directly administer a project, contract, or grant, but delegates the administrative responsibility to another organization.

Blocks 15 & 15a. Security Classification of the Report: Declassification/Downgrading Schedule of the Report. Enter in 15 the highest classification of the report. If appropriate, enter in 15a the declassification/downgrading schedule of the report, using the abbreviations for declassification/downgrading schedules listed in paragraph 4-207 of DoD 5200.1-R.

Block 16. Distribution Statement of the Report. Insert here the applicable distribution statement of the report from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

Block 17. Distribution Statement (of the abstract entered in Block 20, if different from the distribution statement of the report). Insert here the applicable distribution statement of the abstract from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

Block 18. Supplementary Notes. Enter information not included elsewhere but useful, such as: Prepared in cooperation with . . . Translation of (or by) . . . Presented at conference of . . . To be published in . . .

Block 19. Key Words. Select terms or short phrases that identify the principal subjects covered in the report, and are sufficiently specific and precise to be used as index entries for cataloging, conforming to standard terminology. The DoD "Thesaurus of Engineering and Scientific Terms" (TEST), AD-672 000, can be helpful.

Block 20. Abstract. The abstract should be a brief (not to exceed 200 words) factual summary of the most significant information contained in the report. If possible, the abstract of a classified report should be unclassified and the abstract to an unclassified report should consist of publicly-releasable information. If the report contains a significant bibliography or literature survey, mention it here. For information on preparing abstracts see "Abstracting Scientific and Technical Reports of Defense-Sponsored RDT&E," AD-667 000.



DEPARTMENT OF THE ARMY
ST. LOUIS DISTRICT, CORPS OF ENGINEERS
210 NORTH 12TH STREET
ST. LOUIS, MISSOURI 63101

IN REPLY REFER TO

SUBJECT: Wiggins Ozark Camp Dam, MO ID No. 30026
Phase I Inspection Report

This report presents the results of field inspection and evaluation of Wiggins Ozark Camp Dam, MO ID No. 30026.

It was prepared under the National Program of Inspection of Non-Federal Dams.

The St. Louis District has classified this dam as unsafe, emergency, requiring immediate attention because of a large slide on the downstream embankment slope, seepage on the downstream embankment slope and at the toe of the dam and a seriously inadequate spillway which will pass only 4 percent of the Probable Maximum Flood.

SUBMITTED BY. SIGNED 20 MAR 1979
Chief, Engineering Division Date

APPROVED BY. SIGNED 21 MAR 1979
Colonel, CE, District Engineer Date

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/	
Availability Codes	
Avail and/or	
Dist	Special
A	

PHASE I REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam Wiggins Ozark Camp Dam
State Located Missouri
County Located Reynolds County
Stream Adams Hollow Branch of the Middle Fork of the Black River
Date of Inspection 20 November 1978 and 5 and 6 December 1978

Wiggins Ozark Camp Dam was inspected by an interdisciplinary team of engineers, from Reitz & Jens, Inc. under contract with the St. Louis District Corps of Engineers. The purpose of the inspection was to make an assessment of the general condition of the dam with respect to safety, based upon available data and visual inspection to determine if the dam poses hazards to human life and property.

The guidelines used in the assessment were furnished by the Department of the Army, Office of the Chief of Engineers and developed with the help of several Federal and State agencies, professional engineering organizations and private engineers. Based on these guidelines, this dam is classified as a small dam with a high downstream hazard potential. The estimated damage zone from failure of the dam extends three miles downstream from the dam.


Failure would threaten the life and property of eleven families and cause appreciable damage to State Highway 72 and a county road crossing.


Our inspection and evaluation indicates that the dam is deficient in that the spillways do not meet the criteria set forth in the guidelines for a dam having the above size and hazard potential and which require that the spillway be capable of passing a one-half PMF (Probable Maximum Flood). The probable maximum flood is defined as the flood discharge that may be expected from the most severe combination of critical meteorological and hydrologic conditions reasonably possible in the region. The dam will begin to be overtopped by a flood having a discharge (peak and volume) equal to 3% to 4% of the PMF. The spillways will not pass a 1% chance flood (100-year flood) without overtopping the dam. A 100-year flood has a 1% chance of being exceeded in any given year.

Other deficiencies observed by the inspection team were seepage and/or under-seepage at the 2-inch pipe near the east end of the dam and an unstable downstream dam slope as indicated by earth placed as maintenance in a slide reported by Missouri Geological Survey in May 1978.

Seepage and stability analysis records were not available. This is a deficiency.



We recommend the owner take immediate action to correct or control the deficiencies described. A detailed report discussing each deficiency was prepared and submitted to the Governor of Missouri and to the lake owner.


HENRY M. REITZ, President
Reitz & Jens, Inc.


JOHN J. BAILEY, JR., Vice President
Chief Engineer
Reitz & Jens, Inc.



OVERVIEW - 30026



PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
Wiggins Ozark Camp Dam, MO ID No. 30026

TABLE OF CONTENTS

<u>Paragraph No.</u>	<u>Title</u>	<u>Page No.</u>
SECTION 1 - PROJECT INFORMATION		
1.1	General	1
1.2	Description of Project	1
1.3	Pertinent Data	2
SECTION 2 - ENGINEERING DATA		
2.1	Design	5
2.2	Construction	5
2.3	Operation	5
2.4	Evaluation	5
SECTION 3 - VISUAL INSPECTION		
3.1	Findings	6
3.2	Evaluation	8
SECTION 4 - OPERATIONAL PROCEDURES		
4.1	Procedures	9
4.2	Maintenance of Dam	9
4.3	Maintenance of Operating Facilities	9
4.4	Description of Any Warning System in Effect	9
4.5	Evaluation	9
SECTION 5 - HYDRAULIC/HYDROLOGIC		
5.1	Evaluation of Features	10
SECTION 6 - STRUCTURAL STABILITY		
6.1	Evaluation of Structural Stability	11
SECTION 7 - ASSESSMENT/REMEDIAL MEASURES		
7.1	Dam Assessment	12
7.2	Remedial Measures	12
APPENDIX		
A	Hydrologic Computations	

TABLE OF CONTENTS
(Cont.)

LIST OF PLATES

<u>Plate No.</u>	<u>Title</u>
1	Overview - Lake and Environs
2	Location and Vicinity Map
3	Plan and Profile Sheet (in pocket on back cover)
4	Geologic Report
A-1 (11 sheets)	Hydrologic and Hydraulic Computations (Input and Output)

LIST OF INDICES AND PHOTOGRAPH NUMBERS

<u>Index No.</u>	<u>Title</u>
1	Index of Dam Photos (D-1 through D-8)
2	Index of Panorama Photos (P-1 through P-6)
3	Index of Spillway Photos (S-1 through S-11)
4	Index of Valley Below Dam Photos (V-1 through V-2)
5	Index of Seepage Photos (SE-1 through SE-5)

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

a. Authority The National Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of safety inspection of dams throughout the United States. Pursuant to the above, the St. Louis District, Corps of Engineers, District Engineer contracted with Reitz & Jens, Inc. (Contract DACW43-78-C-0162) for a safety inspection of the Wiggins Ozark Camp Dam, MO ID No. 30026.

b. Purpose of Inspection The purpose of the inspection was to make an assessment of the general condition of the dam with respect to safety, based upon available data and visual inspection to determine if the dam poses hazards to human life or property.

c. Evaluation Criteria Criteria used to evaluate the dam were furnished by the Department of the Army, Office of the Chief of Engineers, in "Recommended Guidelines for Safety Inspection of Dams". These guidelines were developed with the help of several Federal agencies and many State agencies, professional engineering organizations and private engineers.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam and Appurtenances

(1) The dam is an earth structure built in Adams Hollow about a mile upstream from the edge of the floodplain of the Middle Fork of Black River. The watershed extends about two miles north of the dam and consists of steeply sloping forested ground. Topographic relief is on the order of 250 feet except for Lee Mountain at the northeastern extremity of the watershed which has a maximum elevation of 1330 or about 550 feet above the damsite. Possibly 40 acres of Adams Hollow above the dam are cleared. There is a concrete chute principal spillway on the east end of the dam and a recently excavated, unlined earth channel emergency spillway at the east abutment.

Immediately upstream of the lake there is another smaller impoundment. This dam is about 500 feet long, about 15 feet maximum height and creates a 5-acre lake with between 25 and 40 acre feet of storage. Its spillway has concrete about 15 feet along the axis of the dam and about 2-1/2 feet vertical dimension. One or more signs of beaver activity were in the area of the dam. In November 1978, this dam and especially the spillway needed considerable maintenance.

Downstream of the main dam there are two concrete weirs constructed across the creek channel. These create small, shallow impoundments.

Topography in the vicinity of the dam is shown on Plate 3.

Pertinent physical data are given in paragraph 1.3 below.

b. Location The dam is located in the northeastern part of Reynolds County about two miles northeast of Lesterville as shown on Plate 2. The dam and lake are located in the N $\frac{1}{2}$ of Section 6, T32N, R2E, and shown on the USGS Lesterville Missouri Quadrangle Sheet, 1968 Edition. The dam is not shown on the 1943 edition of the Lesterville Quadrangle, 15-Minute Series.

Based on information received 24 January 1979 from Dr. James Williams, Missouri Geology and Land Survey, this dam is now owned by Mr. William H. Wenzel, 8000 Bonhomme Avenue, Suite 221, St. Louis, Missouri 63105.

d. Hazard Classification Guidelines for determining hazard classification are presented in the same guidelines referenced in paragraph c above. Based on referenced guidelines this dam is in the High Hazard Classification.

e. Ownership The dam is owned by Marion Wiggins, Ozark Camp, P.O. Box 180, Lesterville, Missouri. There is a proposal to buy this property by Sherwood Forest Camp, 7 North Seventh Street, St. Louis, Missouri, 63101.

f. Purpose of Dam The dam forms a 16-acre recreational lake.

g. Design and Construction History The inspection team was unable to find any design data on this dam. It was reported to the inspection team that a slide or slides had been repaired in the summer of 1968 and the emergency spillway described in paragraph 3.1.d had been excavated at that time. See Plate 4.

h. Normal Operating Procedure Normal rainfall, runoff, transpiration and evaporation all combine to maintain a relatively stable water surface elevation. The maximum water depth ever experienced at the spillway is unknown.

1.3 PERTINENT DATA

a. Drainage Area - 920 acres.

b. Discharge at Damsite -

(1) Discharge at the damsite is through two uncontrolled spillways and a 20-inch pipe under the dam controlled by a hand-operated valve.

(2) Estimated experienced maximum flood at damsite - unknown.

(3) Estimated ungated spillway capacity at maximum pool elevation -

(a) Principal spillway - 272 cfs

(b) Emergency spillway - 256 cfs

(c) Total - 528 cfs

c. Elevation (Feet Above M.S.L.)

(1) Top of dam - 783.5+ (see Plate 3).

(2) Spillway crest -

(a) Principal concrete chute - 779.0

(b) Emergency spillway 780.3

(3) Streambed at centerline of dam - 755⁺ (estimated from survey).

(4) Maximum tailwater - unknown.

d. Reservoir Length of maximum pool - 1800 feet (from aerial photo).

e. Storage

(1) Top of dam - 213 acre feet

(2) Crest of principal spillway - 127 acre feet.

f. Reservoir Surface

(1) Top of dam - 29.6 acres

(2) Spillway crest - 15.9 acres

g. Dam

(1) Type - earth embankment

(2) Length - 700 feet (from survey)

(3) Height - 28.5 feet maximum (from survey)

(4) Top width - 9 feet

(5) Side Slopes -

(a) Downstream - 1V on 2.5H average. Upper portion 1V on 1.6H
(see section at Station 4+00, Plate 3).

(b) Upstream - 1V on 2H to water surface. Portions are steeper
(see paragraph 3.2.b).

(6) Zoning - unknown

(7) Impervious core - unknown.

(8) Cutoff - unknown

(9) Grout curtain - unknown.

h. Diversion and Regulating Tunnel - None

i. Spillways

(1) Principal Spillway: concrete chute at east end of dam, 10 feet wide and four feet deep.

(2) Emergency Spillway: Unlined earth channel excavated in east abutment. Depth about three feet below top of dam. Bottom width about 22 feet. Top width about 55 feet.

j. Regulating Outlets Steel pipe with valve at toe of dam. At the discharge end, this pipe is 20 inches in diameter. The elevation of the upstream end is unknown as is the size of the pipe buried under the dam.

The upper end of this pipe was not visible when the water level was 4-1/2 feet below spillway crest.

SECTION 2 - ENGINEERING DATA

2.1 DESIGN

No design data were found to be readily available.

2.2 CONSTRUCTION

The dam appears to have been constructed sometime between 1950 and 1960. Recently, slides at the east end have been repaired and an emergency spillway channel has been excavated in the east abutment. This work was done after inspection by a State Geologist (see Plate 4).

2.3 OPERATION

The maximum loading on the dam is unknown. The lake level seems to remain stable during average precipitation of 38 inches per year. There are no records of operation of the dam. The present owners have opened the pipe through the dam to keep the lake level several feet below the spillway as a safety measure.

It appears, from the condition of the emergency spillway, that water has flowed through it at some time since completion.

2.4 EVALUATION

a. Availability No engineering data were available.

b. Adequacy No engineering data were available. Therefore, a detailed assessment of design, construction and operation could not be made. The owner should have an engineer, experienced in the design of dams, perform detailed seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams".

However, for the size of dam, materials used and measurements taken, a satisfactory hydrologic/hydraulic evaluation resulted. Also, for the section and presence of the primary spillway plus the visual inspection of a dam with reservoir of at least 15 years of age, the general condition of the dam, when considered by the experienced engineers, indicated that even though a detailed assessment of the design and construction in an analytical sense was not possible, a defensible evaluation of the dam as a structure was feasible.

c. Validity This report is primarily for safety through maintenance and operation and the conclusions and evaluation for this Phase I Inspection are considered adequate for the definitive statement in this report.

SECTION 3 - VISUAL INSPECTION

3.1 FINDINGS

a. General A visual inspection of Wiggins Ozark Dam, Sherwood Forest Camp, was made on 20 November 1978. This inspection was followed by two days (5 and 6 December 1978) of field measurements by a survey party. The training and experience of personnel in the inspections included hydrologic/hydraulic engineering, soils and materials engineering, surveying and structural engineering.

b. Dam This is an earth dam. Both when inspected and during field surveys, the water surface in the reservoir was lower than the principal spillway, resulting from a decision by the owner to lower the lake to reduce probability of recurrence of dangerous slides. A report was available (see Plate 4) from the Missouri Geological Survey which summarized observations and recommendations from a site visit on 24 May 1978. A slide occurred earlier in 1978 in the vicinity of Stations 4+ to 5+. The visible earth tones of the maintenance show the location (D-8).

The top of the dam is narrow, about 9 feet wide (D-1,D-6,D-7,D-8). The downstream slope averages steeper than 1V on 2.5H with the upper half of the downstream slope approaching 1V on 1.6H(D-2,D-5). The upstream slope, while it averages approximately 1V on 2H above the lake surface, in some locations is considerably steeper (D-3,D-8).

An impression, while walking the dam, was that the top of dam has been raised sometime in the past. To maintain width of the raised top, the same upstream dam slope seems to have been continued without changing the toe location of the downstream slope. The raising appears to have been accomplished by steepening the upper portion of the downstream slope.

The top elevation of the dam is irregular; however, the maximum variation is about one foot except within 100 feet west of the concrete spillway where the top is as much as 2-1/2 feet below the lowest portion of the dam to the west of this portion.

Except for the east end of the downstream slope, where brush and small trees were growing, both slopes of the dam were free from any growth higher than a thick grass. No holes or similar signs of digging by animals were seen on any surface of the embankment. The absence of brush or tree growth on the dam surfaces makes an assumption of no animal activity and its probable adverse effect on the safety of the development credible.

On the downstream side of the dam, no areas of hydrophilic plants were observed. The material in the dam appears to have come from a borrow area downstream on the lower west slope of the valley and within the area of the reservoir. The general character of the borrow is residual soils from chemical weathering of the shallow bedrocks in the watershed. Some small rock probably will be mixed throughout the fills placed. Fine-grained soils with relatively low plasticities are the matrix of the fill.

c. Reservoir The shore around the lake, in most portions, was bare as a result of the recent drawdown of the lake surface (P-1,P-2,P-6). In general, the bank of the lake to the west is a gentle slope (P-1,P-2,P-6) without any tree cover except at the north end. The bank along the north end of the east

side (P-3,P-5) is a steep side of the hill with a virgin stand of trees. There is no armor-coating on the reservoir side of the dam (D-3,D-6,D-7,D-8).

Immediately above the end of the full pool formed by this dam is another dam which forms a 5-acre lake. The spillway for this up-valley dam and the embankment (overgrown with trees and brush and also has several signs of currently active beaver colony) need major maintenance to prevent a potential wash-out even if a thunderstorm of low annual probability occurred.

d. Spillways In the original construction, a concrete spillway with vertical sides and flat bottom was built at the east end of the dam (S-2, S-4,S-8,S-9). Width of the spillway was 10 feet; height of the sidewalls 4 feet with a longitudinal slope of 0.7% for a length of 37 feet at its entry and then an 80-foot chute at 6+%. The lower end of this spillway has collapsed and fallen (S-2,S-3) into an eroded ditch.

Maintenance around the concrete spillway has not been good.

As a precautionary measure, earlier in 1978, excavation of a wider emergency spillway in earth approximately 150 feet east of the concrete spillway was begun (S-5,S-7,S-10). The bottom of the earth section as excavated is about one foot higher than the invert of the concrete spillway. While the alignment of the spillway is rough, this 1978 excavation increases the capacity of spillways and helps to bypass flows before the dam is overtopped.

e. Valley Below Dam Two low, massive concrete weirs are built in the creek channel immediately down-valley, then the access road from Missouri Highway 21, then Missouri Highway 21, 4,000 feet south of subject dam and ultimately approximately 1/2-mile beyond the crossing of Missouri 21, the discharge from this valley enters the Middle Fork of the Black River.

The property with the dam was originally developed as a summer camp. Two residential units are at the edge of the valley on the west side and dormitories are on the slope up from the valley on the east side. A recreation service building is immediately downstream (V-1,V-2) on the west slope.

f. Seepage At the extreme east end of the dam, where the earth embankment meets the natural ground surface, seepage is visible (SE-1 thru SE-5). The seepage appears to be around and beneath a 2-inch steel pipe that in turn, was beneath a masonry sill. It is possible this was a location of a seep spring prior to construction of the dam. However, due to its location, it also could have a direct connection into the reservoir.

g. Low-Level Outlet The low-level outlet is a 5/8-inch thick, 20-inch outside diameter pipe at the lower end where it is visible and was flowing at the time of inspection (S-1,S-6,S-11).

h. Prospective Purchasers The Sherwood Camp interests which have a contract to buy this property recognize the deficiencies of this dam and have indicated to the inspection team that they intend to undertake remedial measures or remove the dam when they own the property. Their stated concerns are the instability of the embankment and inadequate spillway capacity. For these reasons, the lake surface has been lowered with the intent to keep it low until repairs and major modifications can be completed.

The Camp Sherwood interests have authorized the start of field investigations and engineering necessary for construction of remedial measures after their purchase of this property about the end of January 1978.

3.2 EVALUATION

The very inadequate spillway capacity, seepage, unstable embankment and low dam crest next to the principal spillway are individual safety deficiencies that could lead to failure of the dam. Existing in combination, they are cause for even greater concern regarding safety of the dam.

For the long, narrow valley with the lake more than 250 feet lower than the tops of bordering ridges, down-valley winds are not unusual. Valley winds with a 1500-foot fetch over the lake will develop waves. Erosion protection on the upstream slope is necessary from the top of dam to below the permanent pool elevation.

The work in the slide of earlier 1978 appears to have filled the depression on the dam slope which developed and is reported in the May 24 report of the Missouri Geological Survey. It is considered to have been temporary maintenance, not permanent repair.

SECTION 4 - OPERATIONAL PROCEDURES

4.1 PROCEDURES

The owner is currently attempting to keep the pool low for the purpose of reducing slides (see paragraph 3.1.b).

4.2 MAINTENANCE OF DAM

Control of vegetation growing on the dam has been adequate except for a small area near the east end. However, maintenance of the embankment around the concrete chute spillway and channel downstream, where scour is undercutting the concrete, is deficient.

4.3 MAINTENANCE OF OPERATING FACILITIES

A valved 20-inch diameter steel pipe is through the dam. When the valve is opened, some of the water stored behind the dam can be drained lowering the lake level behind the dam.

4.4 DESCRIPTION OF ANY WARNING SYSTEM IN EFFECT

The inspection team is not aware of any existing warning system for this dam.

4.5 EVALUATION

Continuing scour at the end of the concrete chute spillway may lead to eventual failure of the spillway and could cause a serious potential of failure of the dam.

The eroded portion of the dam crest west of the chute will allow flow over this portion of the dam embankment before full spillway capacity is utilized.

Reconstruction of this portion of the embankment, to assure full utilization of the existing spillway capacity, would not be difficult and should be completed immediately.

SECTION 5 - HYDRAULIC/HYDROLOGIC

5.1 EVALUATION OF FEATURES

a. Design Data No design data were available.

b. Experience Data The drainage area is developed from USGS Lester-ville, Johnson Shut-Ins, Edgehill and Centerville, Missouri Quadrangles. Also available is a 1"-2000' aerial photo taken on 14 May 1978 by Surdex Corporation. Lake area is measured on a 1"-200' enlargement of a portion of one of these photographs and shown on Plate 1. The spillway and dam layout are from surveys made during the inspection.

c. Visual Observations

(1) The concrete chute principal spillway is in good condition except for the lower end where scour from discharge has caused partial collapse. Sliding and erosion has occurred on the west side of the principal spillway. Hydraulic calculations are based on this short portion of the embankment taken to be the top of dam for overtopping calculations.

(2) The emergency spillway and exit channel are located on the east abutment.

d. Overtopping Potential The spillways are too small to pass the minimum required flood of one-half the probable maximum without overtopping. The probable maximum flood is defined as the flood discharge that may be expected from the most severe combination of critical meteorologic and hydrologic conditions reasonably possible in the region. The dam will start to be overtopped by a flood equal to 3% or 4% of the PMF as it existed and 9% of the PMF is limited local maintenance at the west edge of the concrete spillway. The one-half PMF will overtop the dam to a maximum depth of about 2.3 feet.

Maximum rate of flow over the dam crest will be about 4400 cubic feet per second. Overtopping flow will have a duration of about 8 hours. The dam will be overtopped 0.9-foot by a 100-year frequency flood.

The integrity of the dam during maximum spillway releases cannot be assured.

There is a low dam and 5-acre lake immediately above this impoundment. The volume of water stored in this impoundment is 25 to 40 feet. Failure of this impoundment, in the opinion of the inspection team, would not have a significant impact on the hydrologic or hydraulic analysis related to the one-half PMF.

The effect from rupture of the dam could extend approximately three miles downstream of the dam. There are 11 inhabited homes downstream of the dam which could be severely damaged and lives of the inhabitants lost should failure of the dam occur.

SECTION 6 - STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

a. Visual Observations Visual observations which adversely affect the structural stability of this dam are discussed in Section 3, paragraphs 3.1.b and 3.1.f.

b. Design and Construction Data No design or construction data relating to the structural stability of the dam were found.

c. Operating Records With the exception of the valve on the low level outlet pipe, no appurtenant structures requiring operation exist at this dam. No records of operation of this valve are available.

d. Post Construction Changes The apparent attempt to raise the top of dam by steepening the downstream slope and possibly reducing the top width has contributed to the instability of the downstream slope. Recent maintenance of the slide location described in the State Geologist's report was not adequate, in the opinion of the inspection team, to stabilize this portion of the embankment. This is because the limited lateral extent of the bare earth suggests filling on or against a surface that had slid, a maintenance function not a permanent repair by digging out and replacing the mass of soil in the slide.

e. Seismic Stability Considering the seismic zone (2) in which this dam is located, an earthquake of this magnitude is not expected to cause a structural failure of this dam.

SECTION 7 - ASSESSMENT/REMEDIAL MEASURES

7.1 DAM ASSESSMENT

a. Safety The spillways are inadequate to pass the required one-half Probable Maximum Flood (PMF). Considering the volume of water stored and the valley downstream the one-half PMF is the appropriate spillway design flood.

Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available which is considered a deficiency.

Other safety deficiencies observed by the inspection team were a filled slide location on the downstream slope of the dam and seepage and/or underseepage at the 2-inch pipe.

Several items were noted during the visual inspection by the inspection team which should be corrected or controlled. An armor-coat to protect the reservoir slope of the dam against wave-wash is needed. Erosion protection for the primary spillway is deficient. A portion of the dam crest near the spillway is low and should be raised. The concrete spillway is being undercut by scour at its lower end.

b. Adequacy of Information Due to the lack of engineering design and construction data, the conclusions in this report were based on performance history and external visual conditions. The inspection team considers these data sufficient to support the conclusions herein.

c. Urgency The remedial measures recommended in paragraph 7.2 should be accomplished in the near future. If the safety deficiencies listed in paragraph a are not corrected in the near future, they will continue to deteriorate and lead to a serious potential of failure.

d. Necessity for Phase II Based on the results of the Phase I Inspection no Phase II Inspection is recommended.

e. Seismic Stability This dam is located in Seismic Zone 2. An earthquake of this magnitude is not expected to be hazardous to this dam.

7.2 REMEDIAL MEASURES

a. Recommendations The owner should obtain the services of an engineer experienced in the design and construction of dams to design and observe construction of remedial measures including the following:

(1) Spillway size and/or height of dam should be increased to pass the one-half Probable Maximum Flood (PMF) without overtopping the dam.

(2) Stability and seepage analyses should be performed and appropriate measures designed and constructed to control seepage and underseepage and to

stabilize the downstream slope of the dam. These may include berms, filters and/or drains and constructing a flatter downstream slope.

(3) If the designs under paragraph 7.2.a(1) include continued use of the concrete chute spillway and the present emergency spillway, scour protection at the end of the concrete spillway should be provided and an erosion-resistant sill should be provided in the emergency spillway.

(4) An armor-coat to protect the upstream face of the dam from wave-wash should be provided.

b. O&M Maintenance and Procedures The following O&M maintenance and procedures are recommended:

(1) Raise top of dam adjacent to concrete chute spillway.

(2) Improve control of vegetation growth on the downstream slope of the dam by removal of brush and mowing at sufficient intervals to control future growth.

(3) Periodically check the condition of the steel outlet pipe through the dam for evidence of corrosion and leakage. Water leaking into or out of a corroded outlet pipe could cause piping failure of the earth embankment.

(4) After completion of the remedial measures, detailed inspection of the dam should be made periodically by an engineer experienced in the design and construction of dams. Records should be kept of these inspections and major maintenance.

APPENDIX A
HYDROLOGIC COMPUTATIONS

HYDROLOGIC AND HYDRAULIC ANALYSIS METHODOLOGY

1. The hydrologic analysis used in development of the overtopping potential is based on applying a hypothetical storm to a unit hydrograph to obtain the inflow hydrograph for a reservoir routing. The Probable Maximum Precipitation for those dams in the high hazard potential category is derived and determined from regional charts prepared by the National Weather Service in "Hydrometeorological Report No. 33". Reduction factors have not been applied. A 24-hour storm duration is assumed with the 24-hour rainfall depths distributed over 6-hour periods in accordance with procedures outlined in EM 1110-2-1411 (SPF Determination). The maximum 6-hour rainfall period is then distributed to hourly increments by the same criteria. Within-the-hour distribution is based upon NOAA Technical Memorandum NWS HYDRO-35. The non-peak 6-hour rainfall periods are distributed uniformly. All distributed values are arranged in a critical sequence by the SPF criteria. The final inflow hydrograph is produced by deduction of infiltration losses appropriate to the soil, land use and antecedent moisture conditions.

2. The reservoir routing is accomplished by using Modified Puls routing techniques wherein the flood hydrograph is routed through lake storage. Hydraulic capacities of the spillways and crest of dam are used as outlet controls in the routing. Storage in the pool area is defined by an elevation-area curve. The hydraulic capacity of the spillways and the sloping top of dam is defined by a composite elevation discharge curve.

3. The dam overtopping analysis has been conducted by hydrologic methods for this dam and lake. This computation determines the percentage of the PMF hydrograph that the reservoir can contain without the dam being overtopped. An output summary in the hydrologic appendix displays this information as well as other characteristics of the simulated dam overtopping.

4. The above methodology has been accomplished for this report using the systemized computer program HEC-1 (Dam Safety Version), July 1978, prepared by the Hydrologic Engineering Center, U.S. Army Corps of Engineers, Davis, California. The numeric parameters estimated for this site are listed on Plate 1A. Definitions of these variables are contained in the "User's Manual" for the computer program.

5. Capacities of the spillways were calculated using critical depth at the hydraulic control sections. Energy grade or reservoir elevation was determined by adding critical velocity head plus 0.2 velocity head to allow for velocity distribution, velocity head changes and friction back to the reservoir. The control section for the concrete chute was at its upper end and for the emergency spillway at its crest near the dam centerline.

6. The upstream dam was included in the hydrologic and hydraulic calculations using the HEC-1 computer program as detailed on the attached input-output sheets listed in Plate A-1. In the opinion of the inspection team's hydraulic-hydrologic engineers, the effect of rupture of this dam would have little effect on the conditions existing during a one-half PMF because of the relatively small volume of water impounded.

7. Discharge over the irregular top of dam (the crest is not level) was calculated using a coefficient of 3.0 in the broad-crested weir equation for the sections of dam crest at different elevations. All spillway and overtopping discharges were included in a composite rating curve. Dummy values of 0.1 for dam length, coefficient of discharge and exponent were entered on the \$D card to suppress diagnostic statements in the output. The amount of this dummy flow is never greater than 0.02 cfs.

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 3 AUG 78

1	A	*****	ID # 30026 WIGGINS OZARK CAMP DAM *****						
2	A	*****	DAM SAFETY PROGRAM - U. S. CORPS OF ENGINEERS *****						
3	A	*****	REITZ & JENS, INC. - SEPTEMBER 1978 *****						
4	A	2AR	0 5 -0 -0 -0 -0 -0 -0 -0 -0						-0
5	1	5							-4
6	1	1							
7	J1	0.02	0.03 0.04 0.05 0.50 1.00						
8	K	0	1						1
9	1	*****	INFLOW HYDROGRAPH - SCS METHOD *****						
10	M	1	2 1.052						1
11	P	1	26.6 101 120 130						
12	T								-1 -00
13	W2		0.40						0.02
14	X		-0.20 2.0						
15	K	1	*****	RESERVOIR ROUTING - SPILLWAY AND DAM EQUATIONS *****					
16	1	*****	RESERVOIR ROUTING - SPILLWAY AND DAM EQUATIONS *****						
17	Y								-795.0
18	V1	1							
19	SA	0.00	5.0 9.0 31.0						
20	SF	780	795 800 820						
21	SS	795.0	15.0 3.2 1.5						
22	SD	797.5	3.0 1.5 500.0						
23	K	0							
24	1	*****	SUB-AREA DIRECTLY TRIBUTARY TO WIGGINS DAM *****						
25	4	1	2 0.388						1
26	P	1	26.6 101 120 130						
27	T								-1 -05
28	W2		0.20						0.08
29	X		-0.10 2.0						
30	1	*****	COMBINED HYDROGRAPH *****						
31	1	*****	COMBINED HYDROGRAPH *****						
32	K	1							
33	1	*****	RESERVOIR ROUTING - RATING CURVE SUPPLIED - SLOPING DAM *****						
34	Y								
35	V1	1							-1
36	Y4	779.0	779.2 779.5 780.0 780.6 780.8 780.95						781.0 781.2 781.5
37	Y4	781.8	782.0 782.5 783.0 783.7 784.2 784.5						785.0 786.5 787.5
38	Y5	0.0	3.0 9.0 27.0 56.0 66.4 79.0						82.5 83.0 84.8
39	Y5	216.0	278.0 480.0 753.0 1323.0 2026.0 2675.0						4010.0 8938.0 12230.0
40	SA	0.0	15.91 17.3 53.3						
41	SA	755	779 780 800						
42	SS	779.0							
43	SD	780.95	0.1 0.1 0.1						
44	K	99							

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 3 AUG 78

RUN DATE 01/24/79.
 TIME 11.45.09.

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

RUNOFF HYDROGRAPH AT 1
 ROUTE HYDROGRAPH TO 2
 RUNOFF HYDROGRAPH AT 3
 COMBINE 2 HYDROGRAPHS AT 4
 ROUTE HYDROGRAPH TO 5
 END OF NETWORK

***** ID # 30026 WIGBINS OZARK CAMP DAM *****
 ***** DAM SAFETY PROGRAM - U. S. CORPS OF ENGINEERS *****
 ***** REITZ & JENS, INC. - SEPTEMBER 1978 *****

JOB SPECIFICATION

NO	NHR	NMIN	IDAY	IMR	IMIN	METAC	IPLT	IPRT	NSTAN
288	0	5	-0	-0	-0	-0	-0	-4	-0
			JOPER	NWT	LROPT	TRACF			
			5	-0	-0	-0			

MULTI-PLAN ANALYSES TO BE PERFORMED

RTIOS= .02 .03 .04 .05 .50 1.01
 NPLAN= 1 NRTIO= 6 LRTIO= 1

***** SUB-AREA RUNOFF COMPUTATION *****

***** INFLOW HYDROGRAPH - SCS METHOD *****

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
1	0	-0	-0	1	3	1	-0	-0

HYDROGRAPH DATA

IMYD8	IUM8	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISHOW	ISAME	LOCAL
1	2	1.05	-0.00	1.05	1.00	-0.000	-0	1	-0

PRECIP DATA

SPEE	PMS	R6	R12	R24	R48	R72	R96
-0.00	26.00	101.00	120.00	130.00	-0.00	-0.00	-0.00

LOSS DATA

LROPT	STKPR	DLTKR	RTIOL	ERAIN	STRKS	RTIOK	SIRTL	CNSTL	ALSNV	RTIMP
-0	-0.00	-0.00	1.00	-0.00	-0.00	1.00	-1.00	-08.00	-0.00	.02

CURVE NO = -00.00 WETNESS = -1.00 EFFECT CN = 88.00

UNIT HYDROGRAPH DATA

TC = -0.00 LAG = .40

RECESSION DATA

STRTO = -0.00 ORCSN = -.20 RTIOR = 2.00

UNIT HYDROGRAPH 26 END OF PERIOD ORDINATES: TC = -0.00 HOURS: LAG = .40 VOL = 1.00 109.
 186. 376. 685. 1013. 1144. 1117. 971. 770. 532. 25. 18.
 291. 210. 157. 116. 85. 62. 46. 34. 25. 18.
 16. 11. 8. 5. 3. 1.

MO.DA HR.MM PERIOD RAIN EXCS LOSS COMP Q MO.DA HR.MM PERIOD RAIN EXCS LOSS COMP Q

HYDROGRAPH ROUTING

***** RESERVOIR ROUTING - SPILLWAY AND DAM EQUATIONS *****

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
2	1	-0	-0	1	2	1	-0	-0

ROUTING DATA

QLOSS	CLOSS	AVG	IRCS	ISAME	IOPT	IPMP	LSTR
-0.0	-0.000	-0.00	1	1	-0	-0	-0

NSTPS NSTOL LAG AMSKK X TSK STORA ISPRAT

1	-0	-0	-0.000	-0.000	-0.000	-795.	-0
---	----	----	--------	--------	--------	-------	----

SURFACE AREA= 0. 5. 31.

CAPACITY= 0. 25. 60. 438.

ELEVATION= 780. 795. 800. 920.

CREL SPWID COW EXPW ELEV COOL CAREA EXPL

795.0	15.0	3.2	1.5	-0.0	-0.0	-0.0	-0.0
-------	------	-----	-----	------	------	------	------

DAM DATA

TOPEL	COWD	EXPW	DAMWID
797.5	3.0	1.5	500.

SUR-AREA RUNOFF COMPUTATION

***** SUR-AREA DIRECTLY TRIBUTARY TO WIGGINS DAM *****

ISTAQ	ICOMP	IFCON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
3	0	-0	-0	1	3	1	-0	-0

HYDROGRAPH DATA

IMYNG	IUMG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1	2	.39	-0.00	.39	1.00	-0.000	-0	1	-0

PRECIP DATA

SPEE	PMS	R4	R12	R24	R48	R72	R96
-0.00	26.60	101.00	120.00	130.00	-0.00	-0.00	-0.00

LOSS DATA

LWHT	STKR	DLTKR	RTIOL	FRAIN	STKS	DTIOL	STPL	CNSTL	ALSMX	RTIMP
-0	-0.00	-0.00	1.00	-0.00	-0.00	1.00	-1.00	-85.00	-0.00	.08

CURVE NO = -85.00 WETNESS = -1.00 EFFECT CN = 85.00

UNIT HYDROGRAPH DATA

TC=	-0.00	LAG=	.20
-----	-------	------	-----

RECESSION DATA

STRTO=	-0.00	GRCSN=	-.10	RTTOR=	2.00
--------	-------	--------	------	--------	------

UNIT HYDROGRAPH 14 END OF PERIOD ORDINATES, TC= -0.00 HOURS, LAG= .20 VOL= 1.00

180.	623.	773.	616.	344.	198.	112.	65.	37.	21.
12.	7.	4.	1.						

0 HR.MN PERIOD RAIN EXCS LOSS COMP 0 MO.DA HR.MN PERIOD RAIN EXCS LOSS COMP 0

3% PMF

—

SUM OF 2 HYDROGRAPHS AT		PLAN 1		RATIO		TOTAL	
0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.
1.	1.	1.	1.	1.	1.	1.	1.
1.	1.	1.	1.	1.	1.	1.	1.
2.	2.	2.	2.	2.	2.	2.	2.
2.	2.	2.	2.	2.	2.	2.	2.
3.	3.	3.	3.	3.	3.	3.	3.
9.	9.	9.	9.	9.	9.	9.	9.
15.	15.	15.	15.	15.	15.	15.	15.
20.	20.	20.	20.	20.	20.	20.	20.
24.	24.	24.	24.	24.	24.	24.	24.
26.	26.	26.	26.	26.	26.	26.	26.
28.	28.	28.	28.	28.	28.	28.	28.
29.	29.	29.	29.	29.	29.	29.	29.
52.	52.	52.	52.	52.	52.	52.	52.
54.	54.	54.	54.	54.	54.	54.	54.
83.	83.	83.	83.	83.	83.	83.	83.
110.	110.	110.	110.	110.	110.	110.	110.
129.	129.	129.	129.	129.	129.	129.	129.
291.	291.	291.	291.	291.	291.	291.	291.
216.	216.	216.	216.	216.	216.	216.	216.
153.	153.	153.	153.	153.	153.	153.	153.
110.	110.	110.	110.	110.	110.	110.	110.
106.	106.	106.	106.	106.	106.	106.	106.
67.	67.	67.	67.	67.	67.	67.	67.
40.	40.	40.	40.	40.	40.	40.	40.
25.	25.	25.	25.	25.	25.	25.	25.
18.	18.	18.	18.	18.	18.	18.	18.
14.	14.	14.	14.	14.	14.	14.	14.
12.	12.	12.	12.	12.	12.	12.	12.
PEAK	343.	52.	52.	52.	52.	52.	52.
6-HOUR	155.	1.	1.	1.	1.	1.	1.
24-HOUR	4.	1.34	1.34	1.34	1.34	1.34	1.34
72-HOUR	1.00	34.05	34.05	34.05	34.05	34.05	34.05
TOTAL	25.49	103.	103.	103.	103.	103.	103.
THOUS CU M	77.	127.	127.	127.	127.	127.	127.
AC-FT	95.						
INCHES							
CMS							
CFS							

4% PMF

SUM OF 2 HYDROGRAPHS AT		PLAN 1		HT10 4	
0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.
1.	1.	1.	1.	1.	1.
1.	1.	1.	1.	1.	1.
2.	2.	2.	2.	2.	2.
2.	2.	2.	2.	2.	2.
3.	3.	3.	3.	3.	3.
11.	11.	11.	11.	11.	11.
15.	15.	15.	15.	15.	15.
26.	26.	26.	26.	26.	26.
30.	30.	30.	30.	30.	30.
31.	31.	31.	31.	31.	31.
33.	33.	33.	33.	33.	33.
35.	35.	35.	35.	35.	35.
36.	36.	36.	36.	36.	36.
65.	65.	65.	65.	65.	65.
102.	102.	102.	102.	102.	102.
135.	135.	135.	135.	135.	135.
163.	163.	163.	163.	163.	163.
431.	431.	431.	431.	431.	431.
237.	237.	237.	237.	237.	237.
126.	126.	126.	126.	126.	126.
133.	133.	133.	133.	133.	133.
85.	85.	85.	85.	85.	85.
51.	51.	51.	51.	51.	51.
31.	31.	31.	31.	31.	31.
22.	22.	22.	22.	22.	22.
17.	17.	17.	17.	17.	17.
15.	15.	15.	15.	15.	15.
PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
515.	195.	65.	65.	195.	195.
15.	6.	2.	2.	6.	6.
	1.26	1.68	1.68	1.26	1.26
	31.98	42.61	42.61	31.98	31.98
	97.	129.	129.	97.	97.
	119.	159.	159.	119.	119.

5% PMF

SUM OF 2 HYDROGRAPHS AT										PLAN 1		RTIO 5	
0.	1.	2.	3.	4.	5.	6.	7.	8.	9.	10.	11.	12.	13.
0.	1.	2.	3.	4.	5.	6.	7.	8.	9.	10.	11.	12.	13.
2.	3.	4.	5.	6.	7.	8.	9.	10.	11.	12.	13.	14.	15.
2.	3.	4.	5.	6.	7.	8.	9.	10.	11.	12.	13.	14.	15.
4.	5.	6.	7.	8.	9.	10.	11.	12.	13.	14.	15.	16.	17.
11.	12.	13.	14.	15.	16.	17.	18.	19.	20.	21.	22.	23.	24.
19.	20.	21.	22.	23.	24.	25.	26.	27.	28.	29.	30.	31.	32.
29.	30.	31.	32.	33.	34.	35.	36.	37.	38.	39.	40.	41.	42.
37.	38.	39.	40.	41.	42.	43.	44.	45.	46.	47.	48.	49.	50.
134.	146.	158.	169.	181.	192.	203.	213.	223.	232.	241.	249.	257.	264.
241.	249.	257.	264.	271.	280.	288.	296.	304.	314.	323.	329.	336.	342.
333.	336.	338.	340.	342.	344.	346.	348.	350.	352.	354.	356.	358.	360.
351.	352.	354.	355.	356.	357.	358.	359.	360.	361.	362.	363.	364.	365.
361.	362.	363.	364.	365.	366.	367.	368.	369.	370.	371.	372.	373.	374.
368.	369.	370.	371.	372.	373.	374.	375.	376.	377.	378.	379.	380.	381.
373.	374.	375.	376.	377.	378.	379.	380.	381.	382.	383.	384.	385.	386.
935.	1011.	1066.	1107.	1136.	1159.	1180.	1210.	1247.	1286.	1322.	1356.	1385.	1409.
1322.	1356.	1385.	1409.	1427.	1440.	1450.	1458.	1471.	1483.	1495.	1503.	1511.	1519.
1548.	1598.	1647.	1694.	1734.	1767.	1791.	1809.	1821.	1831.	1840.	1848.	1856.	1864.
1823.	1798.	1803.	1864.	2019.	2374.	3216.	4423.	5403.	5902.	6288.	6675.	7061.	7448.
5936.	5683.	5213.	4603.	3944.	3414.	2997.	2675.	2428.	2244.	2061.	1878.	1695.	1512.
2109.	2012.	1941.	1888.	1842.	1786.	1723.	1660.	1601.	1548.	1494.	1440.	1386.	1332.
1502.	1464.	1436.	1417.	1404.	1394.	1381.	1361.	1341.	1321.	1301.	1281.	1261.	1241.
998.	973.	947.	914.	870.	827.	784.	741.	698.	655.	612.	569.	526.	483.
506.	473.	442.	414.	387.	362.	339.	318.	298.	279.	260.	241.	222.	203.
263.	248.	234.	227.	220.	213.	207.	202.	196.	191.	186.	181.	176.	171.
184.	178.	172.	167.	163.	159.	155.	152.	149.	147.	145.	143.	141.	139.
142.	141.	139.	137.	136.	135.	134.	133.	132.	131.	130.	129.	128.	127.
131.	130.	129.	128.	127.	126.	125.	124.	123.	122.	121.	120.	119.	118.
126.	125.	124.	123.	122.	121.	120.	119.	118.	117.	116.	115.	114.	113.

50% PMF

SUM OF 2 HYDROGRAPHS AT				PLAN 1 RTIO 6			
1.	2.	3.	4.	3.	4.	3.	4.
0.	4.	4.	4.	4.	4.	4.	4.
1.	4.	4.	4.	5.	5.	4.	4.
2.	4.	4.	4.	17.	17.	18.	20.
3.	11.	12.	14.	15.	15.	37.	41.
4.	27.	29.	31.	33.	35.	57.	60.
5.	47.	49.	51.	53.	55.	73.	76.
6.	65.	67.	69.	71.	72.	93.	97.
7.	86.	108.	134.	163.	187.	121.	125.
8.	332.	424.	509.	549.	568.	382.	394.
9.	628.	635.	641.	647.	653.	452.	463.
10.	679.	683.	686.	689.	693.	532.	543.
11.	708.	710.	712.	714.	716.	618.	629.
12.	726.	728.	729.	73.	732.	708.	720.
13.	738.	739.	740.	741.	742.	794.	806.
14.	747.	748.	749.	750.	751.	874.	886.
15.	2150.	2225.	2281.	2323.	2365.	1513.	1513.
16.	2777.	2823.	2858.	2943.	2902.	2499.	2578.
17.	3303.	3396.	3475.	3560.	3587.	2944.	3008.
18.	3605.	3729.	3869.	4014.	4171.	3645.	3664.
19.	10403.	9165.	7876.	6774.	5952.	3620.	3645.
20.	3869.	3767.	3677.	3565.	3439.	4826.	4852.
21.	2866.	2830.	2805.	2786.	2714.	5314.	5314.
22.	1726.	1611.	1504.	1406.	1313.	3311.	3311.
23.	871.	814.	760.	710.	663.	2521.	2521.
24.	442.	414.	387.	362.	342.	1226.	1226.
25.	262.	258.	256.	255.	254.	1145.	1145.
26.	251.	251.	250.	250.	250.	579.	579.
27.	248.	248.	248.	248.	248.	309.	309.
28.	247.	247.	247.	247.	247.	254.	253.
29.	247.	247.	247.	247.	247.	249.	249.
30.	247.	247.	247.	247.	247.	248.	248.
31.	247.	247.	247.	247.	247.	247.	247.
32.	247.	247.	247.	247.	247.	247.	247.
33.	247.	247.	247.	247.	247.	247.	247.
34.	247.	247.	247.	247.	247.	247.	247.
35.	247.	247.	247.	247.	247.	247.	247.
36.	247.	247.	247.	247.	247.	247.	247.
37.	247.	247.	247.	247.	247.	247.	247.
38.	247.	247.	247.	247.	247.	247.	247.
39.	247.	247.	247.	247.	247.	247.	247.
40.	247.	247.	247.	247.	247.	247.	247.
41.	247.	247.	247.	247.	247.	247.	247.
42.	247.	247.	247.	247.	247.	247.	247.
43.	247.	247.	247.	247.	247.	247.	247.
44.	247.	247.	247.	247.	247.	247.	247.
45.	247.	247.	247.	247.	247.	247.	247.
46.	247.	247.	247.	247.	247.	247.	247.
47.	247.	247.	247.	247.	247.	247.	247.
48.	247.	247.	247.	247.	247.	247.	247.
49.	247.	247.	247.	247.	247.	247.	247.
50.	247.	247.	247.	247.	247.	247.	247.
51.	247.	247.	247.	247.	247.	247.	247.
52.	247.	247.	247.	247.	247.	247.	247.
53.	247.	247.	247.	247.	247.	247.	247.
54.	247.	247.	247.	247.	247.	247.	247.
55.	247.	247.	247.	247.	247.	247.	247.
56.	247.	247.	247.	247.	247.	247.	247.
57.	247.	247.	247.	247.	247.	247.	247.
58.	247.	247.	247.	247.	247.	247.	247.
59.	247.	247.	247.	247.	247.	247.	247.
60.	247.	247.	247.	247.	247.	247.	247.
61.	247.	247.	247.	247.	247.	247.	247.
62.	247.	247.	247.	247.	247.	247.	247.
63.	247.	247.	247.	247.	247.	247.	247.
64.	247.	247.	247.	247.	247.	247.	247.
65.	247.	247.	247.	247.	247.	247.	247.
66.	247.	247.	247.	247.	247.	247.	247.
67.	247.	247.	247.	247.	247.	247.	247.
68.	247.	247.	247.	247.	247.	247.	247.
69.	247.	247.	247.	247.	247.	247.	247.
70.	247.	247.	247.	247.	247.	247.	247.
71.	247.	247.	247.	247.	247.	247.	247.
72.	247.	247.	247.	247.	247.	247.	247.
73.	247.	247.	247.	247.	247.	247.	247.
74.	247.	247.	247.	247.	247.	247.	247.
75.	247.	247.	247.	247.	247.	247.	247.
76.	247.	247.	247.	247.	247.	247.	247.
77.	247.	247.	247.	247.	247.	247.	247.
78.	247.	247.	247.	247.	247.	247.	247.
79.	247.	247.	247.	247.	247.	247.	247.
80.	247.	247.	247.	247.	247.	247.	247.
81.	247.	247.	247.	247.	247.	247.	247.
82.	247.	247.	247.	247.	247.	247.	247.
83.	247.	247.	247.	247.	247.	247.	247.
84.	247.	247.	247.	247.	247.	247.	247.
85.	247.	247.	247.	247.	247.	247.	247.
86.	247.	247.	247.	247.	247.	247.	247.
87.	247.	247.	247.	247.	247.	247.	247.
88.	247.	247.	247.	247.	247.	247.	247.
89.	247.	247.	247.	247.	247.	247.	247.
90.	247.	247.	247.	247.	247.	247.	247.
91.	247.	247.	247.	247.	247.	247.	247.
92.	247.	247.	247.	247.	247.	247.	247.
93.	247.	247.	247.	247.	247.	247.	247.
94.	247.	247.	247.	247.	247.	247.	247.
95.	247.	247.	247.	247.	247.	247.	247.
96.	247.	247.	247.	247.	247.	247.	247.
97.	247.	247.	247.	247.	247.	247.	247.
98.	247.	247.	247.	247.	247.	247.	247.
99.	247.	247.	247.	247.	247.	247.	247.
100.	247.	247.	247.	247.	247.	247.	247.

100% PMF

UPSTREAM DAM

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 795.00 25. 0.	SPILLWAY CRFST 795.00 25. 0.	TOP OF DAM 797.50 40. 190.	TIME OF FAILURE HOURS		
RATIO OF PWF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.02	796.68	0.00	34.	105.	0.00	16.33	0.00
.03	797.25	0.00	38.	167.	0.00	16.33	0.00
.04	797.64	.14	41.	280.	.50	16.17	0.00
.05	797.76	.26	42.	417.	.83	16.08	0.00
.50	799.42	1.92	54.	4450.	12.33	16.00	0.00
1.00	800.62	3.12	65.	5904.	14.25	16.00	0.00

WIGGINS OZARK CAMP DAM

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 772.00 127. 0.	SPILLWAY CREST 779.00 127. 0.	TOP OF DAM 780.95 161. 79.	TIME OF FAILURE HOURS		
RATIO OF PWF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.02	780.62	0.00	155.	57.	0.00	14.42	0.00
.03	781.20	.25	166.	104.	3.42	14.08	0.00
.04	781.59	.64	173.	170.	4.92	17.42	0.00
.05	781.92	.97	180.	252.	5.75	16.67	0.00
.50	785.52	4.57	261.	5730.	15.75	16.00	0.00
1.00	787.26	6.31	307.	11456.	16.83	16.00	0.00

ENGINEERING GEOLOGIC REPORT OF THE WIGGINS OZARK CAMP

REYNOLDS COUNTY, MISSOURI

Fritz C. JENKINS, INC.

Just upstream of the center of Sec. 6, T. 32 N., R. 2 E., Lesterville

LOCATION: Quadrangle.

The lake system serving the Ozark Camp is composed of several small lakes downstream of a large dam near the center of Sec. 6. The two small lakes are full flow concrete type structures built in a shut-in area of Adams Hollow. The large lake, constructed several years ago, is about 33 feet high from the lowest point of the valley.

A large slide has developed on the downstream face of the dam at its highest point near the old stream channel. This slide has progressed almost all the way through the crown of the dam and has dropped a considerable distance vertically. The slide does not appear to be fresh in that it probably occurred several months to perhaps as much as a year ago. No water movement through the slide material was noted. Conversation with the landowner indicates that the water level has been kept at a low point via a pipe under the dam but the water level in the lake was approximately 2-3 feet below normal pool on the date of this investigation.

The slopes on the downstream side at the high point appear to be about a 1:1 with flatter slopes to the west in the area where the dam is at a lower height. Large quantities of water move under the core area of the dam to emerge downstream at numerous locations. One leak is present which appears to be a horizontal through bedrock around the left abutment (near the spillway). This leak in all probability did not precipitate the slide but does contribute to keeping portions of the slide area wet.

The principal spillway is approximately 10 feet wide by 4 feet in depth and is constructed of concrete. This chute spillway has some erosion problems on the downstream end where undercutting due to water flow has allowed portions of the lower end to collapse. The emergency spillway is an earthen type spillway off the left abutment just to the east of the principal spillway.

The pipe under the dam appears to be about a 24 inch pipe with a valve, running through the dam into the lake with no riser.

The drainage area serving this lake is approximately 920 surface acres with the lake at full pool estimated to be about 22 acres.

A small lake of about 4 acres is present upstream of the large lake near the tailwaters. This lake was reported to have been constructed some 30 years ago and dams the entire drainage above it. Much beaver activity in the lake and stream has caused the spillway to be dammed on numerous occasions with at least one incident of overtopping of the dam noted. The spillway on the small structure is filled in by mud and other debris from the beavers with a considerable amount of water loss through and under the concrete structures. Failure of this dam would in all probability add considerable quantities of water to the large lakes just downstream.

The large slide on the main dam structure is considered very hazardous as a full lake will cause saturation of the upper part of the dam and thus additional sliding would be expected to take place. If the slide progressed back towards the lake to where water could move through the broken slide material, disastrous collapse of that part of the dam in all probability would occur. The sudden release of water would rapidly move down the valley, probably skipping over the top of the concrete structures below, which may well result in danger to the owner's home just off the floodplain on the west side of the valley. Highway 72-49-21 is present about 3/4 mile downstream as is a barn with numerous cattle. Severe damage to the highway would be expected in case of dam failure.

It was recommended to the landowner on the date of this investigation that the first priority would be to lower the water level in the lake to where only enough water remained to maintain the fish population, i.e. 5-10 feet of water. This water level should be maintained particularly during the spring months of the year so the lake does not fill to normal pool level. The landslide, in other words, must be kept dry until it can be repaired.

Repair of the slide means removal of the failed soil material in that area. The failed area is about 60 yards wide and from the toe of the dam all the way to the top of the dam. This material must be physically removed and then replaced in lifts with adequate compaction. If at all possible, this work should be designed and completed with the advice and supervision of a qualified engineer experienced in foundation problems. In addition to replacing the soil material, an attempt should be made to decrease the steepness of the slope to prevent future slide problems. A minimum slope configuration on this area is recommended to be at least 3:1 rather than 1:1. After the slide has been repaired, a berm could be placed on the toe of the dam which would also in effect prevent further sliding.

In summary, in its present condition, the dam would be considered very hazardous if water is allowed to remain at full pool elevation. Constant surveillance is recommended to keep the water level at a very low elevation. Repair of the slide is somewhat tricky and should be done with adequate supervision. Collapse of the dam in its present condition would result in probable hazardous results downstream.

Thomas J. Dean, Geologist
Applied Engineering & Urban Geology
Geology & Land Survey
May 24, 1978

orig: Marion Wiggins
Ozark Camp
P.O. Box 180
Lesterville, MO




PHOTO INDEX I
FOR
DAM

PREPARED BY
REITZ & JENS, INC

WIGGINS OZARK CAMP DAM
REYNOLDS COUNTY, MO.
DECEMBER 1978


D 2




D



D 1



D 3



DAM


D 6



D 5



D 7








PHOTO INDEX 2
FOR
PANORAMA

PREPARED BY
REITZ & JENS, INC.


WIGGINS OZARK CAMP DAM
REYNOLDS COUNTY, MO.
DECEMBER 1978





P1



P3









PREPARED BY
REITZ & JENS, INC.

WIGGINS OZARK CAMP DAM
REYNOLDS COUNTY, MO.
DECEMBER 1978



SPILLWAYS



5 10 3



SPILLWAYS





PHOTO INDEX 4
FOR
VALLEY BELOW DAM

WIGGINS OZARK CAMP DAM
REYNOLDS COUNTY, MO.
DECEMBER 1978

PREPARED BY
REITZ & JENS, INC.



VALLEY BELOW DAM







PHOTO INDEX 5
FOR
SEEPAGE

WIGGINS OZARK CAMP DAM
REYNOLDS COUNTY, MO.
DECEMBER 1978


PREPARED BY
REITZ & JENS, INC.




SEE PAGE



FINAL SURVEY	DESIGNED	BY	DATE
	ALLOTTED		
	TEMPLATE		
	NO.		
CHECKED			



PLAN OF DAM AND SPILLWAY



AND SPILLWAYS


2




U7-2

13

PLAN OF LAKE



ORIGINAL SURVEY	SURVEYED	BY	DATE
	PLOTTED		
	TEMPLATE		
	AREAS		
NOTE BOOK NO.	AREAS CHECKED		



0 200 300 FT.

780

760

200

180

160

140

120

100

80

SECTION
AT STA

Q OF DAM

7

7

7

160

140

120

100

80

60

40

20

0

SECTION OF DAM
AT STA 4+00

17

0 100 200 400 FT.

Q OF DAM

WATER LEVEL
5 DEC 1978

780

795

760

790

SECTION OF DAM

AT STA 8+00

785

780

11+00

10+00

Q OF DAM

WATER LEVEL
5 DEC 1978

780

760

780

CONCRETE WALLS

SCALES

1" = 10' VERT.

1" = 100' HORIZ.

2.30

FL. 773.52

ERODED AREA

82.5' 37.5'

Q OF DAM
AT STA 2+

3.65'

FL. 779.01

740

770

780

770

WATER
5 DEC

760

760

PROFILE OF
CONCRETE SPILLWAY

750

4+00

3+00

2+00


1+00

0+00

HIGHWAY FEDERAL AID SHEET
PLATE 4-SINGLE PLAN AND CROSS SECTION-LINE & DOT
TELEDYNE NATIONAL TRACING PAPER

INDIANAPOLIS, INDIANA

PRINTED IN U.S.A.



WATERSHED AND OUTFLOW CHANNEL

0 1000 2000 4000 6000 FT



CONCRETE
SPILLWAY

PROFILE OF TOP OF DAM

SCALES

1" = 5' VERT.

1" = 100' HORIZ.

E. OF DAM
AT STA 2+40
780

F.L. 779.01

770

WATER LEVEL
5 DEC 1978

760

LLWAY

SCALES

1" = 10' VERT.

1" = 100' HORIZ.

C. OF DAM
AT STA 1+26

780

770

WATER LEVEL
5 DEC 1978

760

PROFILE OF EARTH SPILLWAY

FLOW CHANNEL

00 6000 FT

795

790

785

780

CONCRETE
SPILLWAY

EARTH
SPILLWAY

3+00

2+00

1+00

0+00

DAM
A 1+26

780

WIGGINS OZARK
CAMP DAM

770

760

PHASE I — INSPECTION

COUNTY I. D. NO 179

REYNOLDS COUNTY, MISSOURI

INVENTORY NO. I. D. 30026

FOR ST. LOUIS DISTRICT, CORPS OF ENGINEERS

REITZ & JENS, INC.
CONSULTING ENGINEERS

ST. LOUIS, MISSOURI
JANUARY 1979